

BID TAB

CLOUGH PIKE LANDSLIDE STABILIZATIONS
PROJECT NO. 502205
ENGINEER'S ESTIMATE: \$1,243,000.00

HAMILTON COUNTY ENGINEER'S OFFICE

BID OPENING: SEPTEMBER 21ST, 2023

NUM.	ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL
T-WALL FAILURE						
1	201	CLEARING AND GRUBBING, INCLUDING TREE REMOVAL	LS	1		
2	202	T-WALL REMOVED	LS	1		
3	202	GUARDRAIL REMOVED	FT	165		
4	203	OFF-SITE DISPOSAL OF DRILLING SPOILS	CY	250		
5	253	FULL DEPTH PAVEMENT REPAIR	SY	100		
6	511	12"X12" GRADE BEAMS ON DRILLED SHAFTS	LF	150		
7	524	36" REINFORCED CONCRETE DRILLED SHAFTS (INCLUDES TEMPORARY CASING)	LF	375		
8	524	30" REINFORCED CONCRETE DRILLED SHAFTS (INCLUDES TEMPORARY CASING)	LF	600		
9	524	24" UNREINFORCED CONCRETE DRILLED SHAFTS	LF	330		
10	601	ROCK CHANNEL PROTECTION, (RCP) WITHOUT GEOTEXTILE FABRIC, TYPE A	CY	300		
11	601	ROCK CHANNEL PROTECTION, (RCP) WITH GEOTEXTILE FABRIC, TYPE B	CY	6		
12	606	GUARDRAIL, TYPE MGS WITH STEEL POSTS	LF	100		
13	606	MGS ANCHOR ASSEMBLY TYPE E	EA	1		
14	606	MGS ANCHOR ASSEMBLY TYPE T	EA	1		
15	614	MAINTAINING TRAFFIC	LS	1		
16	623	CONSTRUCTION LAYOUT STAKES AND SURVEYING	LS	1		
17	624	MOBILIZATION	LS	1		
18	644	CENTER LINE	LF	150		
19	644	EDGE LINE	LF	150		
20	659	SEEDING & MULCHING	SY	450		
21	671	EROSION CONTROL MAT	SY	450		
22	SPL	ACCESS BENCH & SWITCHING STREAM TO REMOVE/INSTALL WALLS	LS	1		
23	SPL	TEMPORARY SEDIMENT & EROSION CONTROL	LS	1		
24	SPL	TEMPORARY SHORING	LF	75		
25	SPL	GRAVITY BLOCK WALL (INCLUDES SELECT GRANULAR BACKFILL)	SF	1,630		
26	SPL	MAILBOX SUPPORT SYSTEM	EA	3		
LANDSLIDE EAST OF 5-MILE						
27	201	CLEARING AND GRUBBING, INCLUDING TREE REMOVAL	LS	1		
28	202	GUARDRAIL REMOVED	FT	200		
29	202	CULVERT PIPE REMOVED	FT	43		
30	203	OFF-SITE DISPOSAL OF DRILLING SPOILS	CY	340		
31	253	FULL DEPTH PAVEMENT REPAIR	SY	70		
32	254	PAVEMENT PLANING (1.5")	SY	550		
33	441	1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448) PG64-22	CY	28		
34	524	30" REINFORCED CONCRETE DRILLED SHAFTS	LF	1,280		
35	524	24" UNREINFORCED CONCRETE DRILLED SHAFTS	LF	786		
36	606	GUARDRAIL, TYPE 5	LF	200		

